

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 20 2001
11-30-01
CONSERVATION DIVISION
WICHITA, KS

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21787-0000

LEASE NAME Bryant A

WELL NUMBER 1

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 19 RGE. 30 (E) or (W)

COUNTY Lane

Date Well Completed 9/14/01

Plugging Commenced 11/13/01

Plugging Completed 11/13/01

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 S. Broadway, Suite 710 Wichita, KS 67202

PHONE (316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 23, 2001 (date)

by District 1, Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? No, attached to ACO-1 earlier

Producing Formation Marmaton Depth to Top 4479 Bottom 4501 T.O. 4640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		surface	207	8 5/8"	206'	none
		production		5 1/2"	4628'	1297'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
First plug at 1300' w/80 sacks through drill pipe (60/40 poz + 6% gel), Second plug at 740' w/50 sacks cement through drill pipe (60/40 poz + 6% gel), Third plug at 240' w/40 sacks cement through drill pipe (60/40 poz + 6% gel), final plug at 40' w/10 sacks cement through drill pipe (60/40 poz + 6% gel)

Name of Plugging Contractor Express Well Service License No. 6426

Address P.O. Box 19 Victoria, Kansas 67671-0019

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Earl M. Knighton, Jr.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Earl M. Knighton Jr.

(Address) 221 S. Broadway, Suite 710
Wichita, Kansas 67202

DAVID D. MONTAGUE
Notary Public - State of Kansas
My Appt. Expires 9/30/03

AND SWORN TO before me this 30th day of NOVEMBER, 2001

David D. Montague
Notary Public

My Commission Expires: 9-30-03

OR