

15101200050000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Lane \_\_\_\_\_ County. Sec. 4 Twp. 19 Rge. 30 (E) W (W)

Location as "NE/CNW&SW¼" or footage from lines C NE NE

Lease Owner Leo J. Dreiling Oil Co.

Lease Name Bockelman Well No. 1

Office Address Route #2, Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-3 1970

Application for plugging filed 7-3 1970

Application for plugging approved 7-3 1970

Plugging commenced 7-3 1970

Plugging completed 7-3 1970

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug was set at 1025' with 70 sacks cement  
2nd plug was set at 250' with 25 sacks cement  
3rd plug was set at 40' with 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling


LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 70

My commission expires September 19, 1970

JOSEPH A. HESS

Notary Public.



# L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

## WELL LOG

Company Leo J. Dreiling Oil Co.  
Route #2  
Victoria, Kansas 67671

Farm Bockelman No. 1

Total Depth 4690'

Comm. 6-23-70 Comp. 7-3-70

Contractor L. J. Dreiling & Sons, Inc.  
Victoria, Kansas 67671  
Casing Record Cement Record  
225' - 8 5/8" 160 sacks cement

15' 10" 20005.0000

Sec. 4 Twp. 19 Rng. 30

Location C NE NE

County Lane

Elevation: 2884' K. B.  
2881' D. F.  
2879' G. R.

Production:

Figures Indicate Bottom of Formations

0'	70'	Surface Clay
70'	170'	Sand
170'	225'	Shale
225'	900'	Shale & Sand
900'	1230'	Shale
1230'	1480'	Shale & Sand
1480'	1629'	Shale
1629'	1670'	Anhydrite with 12' Shale
1670'	1980'	Shale
1980'	2173'	Red Bed with Salt
2173'	2179'	Anhydrite
2179'	2216'	Shale
2216'	2234'	Anhydrite
2234'	2325'	Shale & Lime
2325'	2565'	Shale & Lime
2565'	2770'	Shale & Lime
2770'	2953'	Lime & Shale
2953'	3077'	Lime & Shale
3077'	3235'	Shale & Lime
3235'	3416'	Lime & Shale
3416'	3587'	Lime and Shale
3587'	3720'	Lime & Shale
3720'	3850'	Lime & Shale
3850'	3910'	Lime & Shale
3910'	3945'	Lime
3945'	3956'	Lime & Shale
3956'	3995'	Lime (K.C.)
3995'	4095'	Lime
4095'	4190'	Lime
4190'	4265'	Lime
4265'	4361'	Lime
4361'	4417'	Lime
4417'	4463'	Lime
4463'	4490'	Lime
4490'	4560'	Lime
4560'	4574'	Lime
4574'	4611'	Lime
4611'	4665'	Lime (Miss.)
4665'	4690'	Lime
4690'	T.D.	

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS)  
                                  )ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc, upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Bockelman #1.



Subscribed and sworn to before me this 10th day of July, 1970

My Commission expires: September 19, 1970

*Leo F. Dreiling*  
\_\_\_\_\_  
LEO F. DREILING

*Joseph A. Hess*  
\_\_\_\_\_  
JOSEPH A. HESS NOTARY PUBLIC