

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

API NUMBER 101-20,389-0000

LEASE NAME Goering

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 4 TWP. 19S RGE. 30 (X) or (W)

COUNTY Lane

LEASE OPERATOR WHITETAIL CRUDE, INC

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE# (785)798-3641 OPERATORS LICENSE NO. 31627

Date Well Completed 6/24/79

Character of Well Oil

Plugging Commenced 2/22/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/25/00

The plugging proposal was approved on 2/21/00 (date)

by Mike Maier/Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation Lansing/Kansas City Depth to Top _____ Bottom _____ T.D. 4597

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				4 1/2	4561	-0-
				8 5/8	288	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so
Hooked to 2 7/8" tubing, spotted 20 sks 60-40 6% gel on bottom, tried to pull casing, could not. hooked up to 4 1/2 and pumped 150 sks of 60-40 6% gel and pumped down casing, casing went on vacuum. Hooked onto 8 5/8 and pumped 75 sks of cement @ 250 PSI, shut in @ 200 PSI. Hooked back up to 4 1/2 pumped another 75 sks of cement & 100# hulls. 2/25/00 topped casing off to surface 50 sks 400#

Name of Plugging Contractor Swift Services, Inc License No. 32382

Address P O Box 466, Ness City, KS 67560


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzier, President Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters hereinafter contained and the log of the above-described well as filed in the same are true and correct. STATE CORPORATION COMMISSION

(Signature) Mike J. Fritzier

(Address) P O Box 544, Ness City, KS 67560-0544



JUN 1 2000
 6-1-00

SUBSCRIBED AND SWORN TO before me this 26th day of May, X9 2000

Debra Kerr
 Notary Public

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM

