

LEASE NAME Goering

WELL NUMBER #3

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 4 TWP. 19S RGE. 30W (E) or (W)

COUNTY Lane

Date Well Completed 9/19/79

Plugging Commenced 5/8/01

Plugging Completed 5/8/01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE# (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/7/01 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom PB T.D. 4370

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	323	JUN 11 2001
				4 1/2	4537	680' 6-11-01
						CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each section.
Sanded perfs off & spotted 4 sks of cement with a dump bailer @ 4200'. Ran Tubing & packer to 1220' & checked the pipe-it held 300#. Shot the pipe in two @ 1200' & tried to pull-could not Pumped 80 sks & 200# hulls & displaced to 1200'. Cut off 4.5" @ 680', pulled it and pumped a 50 sk plug. Pulled 4.5" to 330' & pumped a 40 sk plug. Pulled pipe out & topped off with 20 sk. Job completed. Cement did not fall.

Name of Plugging Contractor Swift Services, Inc License No. _____

Address P O Box 466, Ness City, KS 67560-0466


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 7th day of June, 2001, at _____

Debra Kerr
Debra Kerr Notary Public

My Commission Expires: 4/20/2005

USE ONLY ONE SIDE OF EACH FORM

OR