

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Goering
WELL NUMBER 4
990 Ft. from N Section Line
330 Ft. from W Section Line
SEC. 4 TWP. 19S RGE. 30W XX or (W)
COUNTY Lane
Date Well Completed 10/1/79
Plugging Commenced 11/23/98
Plugging Completed 11/23/98

EASE OPERATOR Whitetail Crude, Inc
ADDRESS P O Box 544, Ness City, KS 67560-0544
PHONE (785-798-3641) OPERATORS LICENSE NO. 31627

Character of Well Oil
Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on _____ (date)
by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? _____ if not, is well log attached? _____

Producing Formation Kansas City Depth to Top 4370 Bottom 4499 T.D. 4556

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Kansas		0	322	8 5/8	322	-0-
		0	4504	4 3/4	4504	Pulled 591' of 4 3/4 out.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Sanded bottom off to 4200', spotted 4 sacks of cement with dump bailer. Perforated casing @ 1300' and pumped 90 sks of 60/40 6% & displaced to 700'. Well went on a vacuum, pumped 25 sks & 50# of bulls and displaced to 900' @ 300 PSI. Shot casing off @ 591' pumped 35 sks, pulled to 340' & pumped 50 sks, pulled to 40' and pumped 20 sks. Pulled the rest and topped the well off.


Name of Plugging Contractor: Allied Cementing Co Inc License No. _____
Address P O Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed thereon and the same are true and correct, so help me God.

(Signature) Mike J. Fritzler
(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 98

Debra Kerr
Notary Public Debra Kerr

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM