

15-101-20774-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 22 TWP. 16S RGE. 29W E/W
Location as in quarters or footage from lines:
15' N of C NW NW

Lease Owner K.R.M. Petroleum Corp.
Lease Name Roberts Well No. 2-22
Office Address 1900 Grant St., Suite 300, Denver, Co. 80203
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed May 13, 1983
Application for plugging filed May 23, 1983
Plugging commenced May 13, 1983
Plugging completed May 13, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Permission was obtained

Name of Conservation Agent who supervised plugging of this well Paul Luthi, Dodge City, Ks.

Producing formation _____ Depth to top _____ bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	374	23	9 jts. J-55	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

The Roberts #2-22 was plugged with 195 sx 60/40 poz, 2% gel,
3% cc. Plugs were staged at: 50 sx at 2170', 70 sx at
1395', 40 sx at 403', 10 sx at 40', 15 sx in rat hole and 10 sx
in mouse hole. Halliburton cemented the well with Don Ubel
giving plugging orders from Dodge City, and state pluggger
Paul Luthi on location during plugging operation.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Sedgwick, ss. Driller
Pamalyn C. Allen (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Pamalyn C. Allen
453 S. Webb Rd., P.O. Box 18611
Wichita (Address) Kansas 67207

SUBSCRIBED AND SWORN TO before me this 23 day of May, 19 83

Kathleen G. Quinn
Kathleen G. Quinn Notary Public.
STATE CORPORATION COMMISSION

My Commission expires: March 20, 1987

MAY 24 1983

CONSERVATION DIVISION
Wichita, Kansas



ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372



WELL LOG

15-10120774-0000

WELL NAME: Roberts #2-22

WELL LOCATION: Sec. 22-16S-29W

Lane County, Kansas

OPERATOR: K.R.M. PETROLEUM CORP.

COMMENCED: May 4, 1983

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: May 13, 1983

CASING RECORD: _____

8 5/8" set at 374'

FORMATION:

FROM:

TO:

SAND & SOIL	0	411'
CLAYS	411'	534'
RED BED & CLAY	534'	1966'
ANHYDRITE & BLACK SHALE	1966'	2011'
RED ROCK & SHALE	2011'	2168'
LIME	2168'	2200'
RED ROCK & SHALE	2200'	2450'
LIME & SHALE	2450'	4571'

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1983

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED

15th N of C NW NW, Sec. 22-16S-29W, Lane County, Kansas TO THE BEST OF MY


KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

Pamelyn C. Allen
Pamelyn C. Allen, Accountant

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23rd DAY OF May, 1983

MY APPOINTMENT EXPIRES: March 20, 1987



Kathleen G. Quinn
Kathleen G. Quinn NOTARY PUBLIC