

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84
RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
(File One Copy)

AUG 14 1985
8-14-85
CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-101-21,194-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Gross Petroleum Management, Inc. OPERATORS LICENSE NO. 9726

ADDRESS 900 Building of the Southwest, Midland, TX 79701 PHONE # (915) 682-8319

LEASE (FARM) A. Goering WELL NO. 1 WELL LOCATION 4620' FSL COUNTY LANE

SEC. 30 TWP. 19S RGE. 30 (H) or (W) TOTAL DEPTH 4690' KB PLUG BACK TO —

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 358' CEMENTED WITH _____ SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK NO JUNK IN HOLE NO

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL BALANCED Plug METHOD - 185 sx 50-50 Pozmix 4% Gel 3% CaCl₂
1st Plug @ 2020'-50sx; 2nd Plug @ 1150'-50sx;
3rd Plug @ 380'-50sx; 4th Plug @ 40' - 1sk Halls w/ Wood Plug; 10sx; Rathole - 15sx Mousehole - 10sx

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No. To follow IS ACO-1 FILED? No
(If not, explain) To accompany ACO-1 from Midland, TX

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5:40am 7/18/85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

BEREDCO, Inc. (Howard Cain) PHONE # (316) 653-2463

ADDRESS P.O. Box 30, Holsington, Kansas 67544

PLUGGING CONTRACTOR DOWELL - SCHLUMBERGER LICENSE NO. _____

ADDRESS 905 E. Ninth (P.O. Box 219) Hays, Kansas 67601 PHONE # (913) 625-3476

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: CJ Menden
(Operator or Agent)

DATE: August 14, 1985