

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-101-21,526-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Voshell WELL NO. 3 WELL LOCATION C SE COUNTY Lane

SEC. 13 TWP. 19S RGE. 29 ~~(E) (W)~~ TOTAL DEPTH 4685' PLUG BACK TD         

Check One:

OIL WELL          GAS WELL          D & A x SWD or INJ WELL          DOCKET NO.         

SURFACE CASING SIZE 8 5/8" SET AT 260.04' CEMENTED WITH 170 SACKS

CASING SIZE          SET AT          CEMENTED WITH          SACKS

PERFORATED AT         

CONDITION OF WELL: GOOD x POOR          CASING LEAK          JUNK IN HOLE         

PROPOSED METHOD OF PLUGGING Circulate heavy mud 15 minutes. 1st plug at 2170'-50 sx. 2nd

plug at 1200'-80 sx. & 1 sack of hulls. 3rd plug at 290'-40 sx. 4th plug at 40'-10 sx.

Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 10:45 a.m. on 10-15-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wilmer Dreiling PHONE # (913) 726-4850

ADDRESS 408 Jefferson, Ellis, KS 67637

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack L. Wharton  
(Operator or Agent)

DATE: 12-04-89

RECEIVED  
STATE CORPORATION COMMISSION  
DEC - 5 1989  
12-5-89  
CONSERVATION DIVISION  
Wichita, Kansas