

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # SPUD 9/11/78 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR JHS Energy, Inc KCC LICENSE # 31645
(owner/company name) (operator's)

ADDRESS 1720 S Bellaire St, Ste 1209 CITY Denver

STATE CO ZIP CODE 80222 CONTACT PHONE # (303) 757-8811

LEASE Paris "A" SWD WELL# 2 SEC. 14 T. 19 R. 29 (East/West)

S/2 S/2 SE - SPOT LOCATION/0000 COUNTY Lane

390' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1320' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ☐ GAS WELL ☐ D&A ☐ SWD/ENHR WELL ☒ DOCKET# D-19,464

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 259' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4659' CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Miss 4637-49'

ELEVATION 2816'/2821' T.D. 4660' PBTD 4659' ANHYDRITE DEPTH 2152-78'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD ☐ POOR ☐ CASING LEAK ☒ JUNK IN HOLE ☒

PROPOSED METHOD OF PLUGGING as directed by KCC

See attachment for additional information
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? not sure
If not explain why? Log not available, no ACO-1 in file

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Richardson PHONE# 803 757-8811

ADDRESS 1720 S Bellaire St #1209 City/State Denver, CO 80222

PLUGGING CONTRACTOR DS & W Well Servicing KCC LICENSE # 6901
(company name) (contractor's)

ADDRESS Clafflin, KS PHONE # (316) 587-3361

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Will notify KCC

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4/7/97 AUTHORIZED OPERATOR/AGENT: W Richardson
(signature)

JHS

JHS ENERGY, INC
Oil and Gas Investments and Management
1720 S. Bellaire Street, Suite 1209
Denver, CO 80222
(303) 757-8811
Fax: (303) 757-1911

15-101-20340-0007

April 7, 1997

Kansas Corporation Commission
Conservation Division
130 South Market - Room 2078
Wichita, KS 67202

Re: Application to Plug and Abandon
Paris "A" #2 SWD
Lane County, Kansas
Docket #D-19,464

Gentlemen:

Attached please find our application to plug and abandon the subject well. We plan to start the work soon after receiving your approval and after receiving plugging instructions from Mr. Richard W. Lacey in your Dodge City office.

JHS Energy succeeded Buffalo Operating as operator in November of 1996. Please contact me with any questions or discussion.

Sincerely,



William E. Richardson, P.E.
Operations Manager

attachment

RECEIVED
KANSAS CORP COMM
1997 APR 11 A 10:51



JHS ENERGY, INC
Oil and Gas Investments and Management
1720 S. Bellaire Street, Suite 1209
Denver, CO 80222
(303) 757-8811
Fax: (303) 757-1911

15-101-20340-0007

April 7, 1997

Additional Information for Application to Plug and Abandon
Paris "A" #2 SWD
Lane County, Kansas
Docket #D-19,464

Well drilled in 1978 and completed as SWD. No records to indicate that an API number was issued. Current operator has no copies of logs run in well.

On October 9, 1978, the production casing was cemented from 1050' to the surface using 1-inch tubing and 150 sacks cement.

JHS Energy succeeded Buffalo Operating as operator in November of 1996.

The well failed MIT on November 13, 1996. Operator attempted to pull tubing and packer but tubing parted. Attempts to recover fish were unsuccessful and the well was abandoned. Junk left in hole: packer at 4208', top of tubing at 3039'.

Production casing will not be recovered when well plugged.

Surface Pond Permit #PO9022 attached to this lease. This pit has been closed, at an unknown time, and there are no records to indicate the closure. Operator requests that this pit permit be closed.

William E. Richardson, P.E.
Operations Manager

RECEIVED
KANSAS CORP COMM
1997 APR 11 A 10:51

RECEIVED APR 03 1997



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

FINAL NOTICE

15-101-20340-0001

DATE: March 31, 1997
TO: JHS Energy, Inc.
FROM: District #1
SUBJECT: 5-Year MIT Retest
WELL: Paris A #2
S/2 S/2 SE 14-19S-29W
Lane County, KS
Docket #D-19,464

COPY

Dear Sir:

The MIT on this well was due in October of 1996. Please be aware that failure to test the well could result in the imposition of an Administrative Penalty and could cause the well to be shut-in. All injection wells in the state are required to be tested. This includes temporarily abandoned injection and disposal wells.

This letter is to advise you that the above captioned well(s) must be tested without further delay. You must contact the district office captioned above by April 16, 1997, to schedule a date for the test. Any questions regarding the type of test, equipment needed, etc., should be discussed when scheduling the date for the MIT.

If the injection well(s) are not tested by April 30, 1997, then the captioned repressuring or disposal well will be immediately shut-in by the district staff. Injection into the well(s) after shut-in will result in an administrative penalty of \$2500 being imposed by the Kansas Corporation Commission.

Failure to MIT the well(s) by May 16, 1997, will result in a \$1000 administrative penalty being imposed and the well will continue to be shut-in until the fine is paid and the MIT is performed and passed.

Operators have the responsibility to prepare the well for the test prior to the scheduled time. This includes the appropriate means for pressuring up the well and the bradenhead being prepared for measuring the pressures. A representative of the operator should be at the site during the testing.

Your cooperation in performing the required MIT will be greatly appreciated. If you have questions or require additional information, please do not hesitate to call 316-225-6760.

Sincerely,

Richard W. Lacey

RECEIVED
KANSAS CORP COM
1997 APR 11 4 10:51



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 11, 1997

JHS Energy Inc
1720 S Bellaire St Ste 1209
Denver CO 80222

Paris "A" SWD #2
API 15-101-20,340-000/
390 FNL 1320 FEL
Sec. 14-19S-29W
Lane County

Dear Bill Richardson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760