

1 050746

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,661-0000
NW SW SE, SEC. 1, T 17 S, R 29 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: Kansas Corporation Commission
Name & Address 202 W. 1st Street
Wichita, KS 67202-1286

Lease Name Bryant Well # 1
County Lane
Well Total Depth 4450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 15 Month: January Year: 19 86

Plugging proposal received from Richard W. Lacey

(company name) KCC (phone) 316-225-6760

were: 4 1/2" at 4449' PBT 4440' Perfs N/A

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer

2nd plug shoot hole in 4 1/2" pipe at 1305' and pump 300 sx cement down 4 1/2".

If no returns, pump 125 sx cement down 8 5/8" x 5 1/2" annulus.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 am Day: 15 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 4 sx cement on top of sand through bailer, 2nd plug pumped 300 sx cement down 4 1/2", 3rd plug pumped 125 sx cement down 8 5/8" x 4 1/2" annulus.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1986
CONSERVATION DIVISION

4 1/2" Maximum pressure 1100 psi and shut in 600 psi
Annulus 0 pressure

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)