

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20053-00-00  
Spot: CSWSE Sec/Twnshp/Rge: 1-17S-29W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: BRYANT Well Number: 1  
County: LANE Total Vertical Depth: 2195 feet

Operator License No.: 5552  
Operator Name: GORE OIL COMPANY  
Address: PO BOX 2757  
WICHITA, KS 67201

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 244  
Production: Size 4.5 feet: 2194  
Liner: Size feet:

71.34

Well Type: SWD UIC Docket No: D16943.0 Date/Time to Plug: 11/01/2000 2:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY WRAY Company: GORE OIL Phone: (316) 263-3535

Proposed Plugging Method: CASING SWAB IN HOLE TOP @ 1410' SANDED IN. RAN TUBING IN HOLE TO 1406'. PUMPED 80 SX CMT. CEMENT CIRCULATED TO SURFACE PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 20 SX CMT. 8 5/8 X 4 1/2 ANNULUS CEMENT AT SURFACE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/01/2000 4:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 1765-1890'. CASING SWAB IN HOLE TOP @ 1410' SANDED IN. RAN TUBING IN HOLE TO 1406'. PUMPED 80 SX CMT. CEMENT CIRCULATED TO SURFACE PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 20 SX CMT. 8 5/8 X 4 1/2 ANNULUS CEMENT AT SURFACE.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 01 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Kevin Strube (TECHNICIAN)

INVOICED

DATE 11/21/00

NOV 08 2000

INV. NO. 2001061005

MP