

1 050747

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,668 -0000

SW NW SE, SEC. 1, 'T 17 S, R 29 W/MEX

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Newman Well # 1

Operator: Kansas Corporation Commission

County Lane

Name & Address 202 W. 1st Street

Well Total Depth 4600 feet

Wichita, KS 67202-1286

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 am Day: 15 Month: January Year: 19 86

Plugging proposal received from Richard W. Lacey

(company name) KCC (phone) 316-225-6760

were: 4 1/2" at 4600' PBTD 4440' Perfs N/A

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer

2nd plug shoot hole in 4 1/2" pipe at 1332' and pump 300 sx cown 4 1/2". If no returns, pump 125 sx cement down 8 5/8" x 5 1/2" annulus.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 pm Day: 15 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of sand through bailer, 2nd plug shot hole in pipe at 1332'. Pumped 300 sx cement down 4 1/2". Pumped 125 sx cement down 8 5/8" x 5 1/2" annulus.

4 1/2" Maximum pressure 1000 psi and shut in 400 psi

8 5/8" Maximum pressure 500 psi and shut in 500 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1986

CONSERVATION DIVISION