

1 070048

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,238-0000

W/2,NW/5W, SEC. 2, T. 17 S, R. 29 (NW)

1980 feet from S section line

1950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Gill D Well # 1

Operator: Chief Drly. Co. Inc.

County Lane 150.15

Name & Address 905 Century Plaza

Well Total Depth 4620 feet

Wichita, Ks 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 328

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drly. Co. License Number 5883

Address Wichita, Ks.

Company to plug at: Hour: 3:45 PM Day: 9 Month: 11 Year: 19 85

Plugging proposal received from Herald Dinkie

(company name) Warrior Drly. (phone) 316-262-3791

work: To fill hole with heavy mud and spot plugs through drill pipe. Elev. 2797
Any. 2235

1st plug 2150' with 50 sx. cem. 2nd plug at 1350' with 50 sx. cem.

3rd plug at 750' with 40 sx. cem. 4th plug at 400' with 40 sx. cem.

5th plug at 40' with 10 sx. cem. 6th plug Circulate rat hole with

15 sx. cem. 7th plug Circulate mouse hole with 10 sx. cem.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 PM Day: 9 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx. cem. 2nd plug at

1350' with 50 sx. cem. 3rd plug at 750' with 40 sx. cem.

4th plug at 350' with 40 sx. cem. 5th plug at 40' with

wiper plug and 10 sx. cem. 6th plug circulated rat hole with

15 sx. cem.

Remarks: 60/40 Pozmix 2% gel. 3% cc, Allied Cementers

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 12-9-85

NOV 18 1985

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 11319