

1050451

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,124-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5232

Lease Name Zerener Well # 1

Operator: Pinto Petroleum

County Lane 167.28

Name & Address P. O. Box 11184

Well Total Depth 5147 feet

Wichita, KS 67211

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 292 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Strata Drilling License Number 6188

Address 5619 8th Street, Bos 342, Great Bend, KS 67530

Company to plug at: Hour: 10:00 pm Day: 8 Month: February Year: 19 85

Plugging proposal received from Howard Cain

(company name) Strata (phone) 316-793-7971

were: to fill hole with heavy mud and spot cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
2-12-85
FEB 12 1985

1st plug at 2200' with 50 sx cement

2nd plug at 1140' with 50 sx cement

3rd plug at 720' with 40 sx cement

CONSERVATION DIVISION
Wichita, Kansas

4th plug at 330' with 40 sx cement

5th plug ^{solid bridge} hulls - plug at 40' Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)
cement to surface with 10 sx cement

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with
Plugging Operations attended by Agent?: All _____ Part _____ None X
10 sx cement

Operations Completed: Hour: 11:30 pm Day: 8 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1140' with

50 sx cement, 3rd plug at 720' with 40 sx cement, 4th plug at 330' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10

sx cement, 7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate

mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy to client) observe this plugging.

DATE 2-14-85

Signed Richard W. Lacey SQ (TECHNICIAN)

INV. NO. 6981 28 MAR 15 1985