

To: 1 090836 8-12
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-21,746-0000
C W/2 NE, SEC. 8, T 19 S, R 30 W/X
1320 feet from NXX section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5010
Operator: Knighton Oil Company, Inc.
Name:
Address 221 S. Broadway, Ste. 710
Wichita, KS 67202

Lease Name Bryant Well # 1
Lane
County 152.75
Well Total Depth 4700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 12 Month: 8 Year: 19 97

Plugging proposal received from Mike
(company name) Duke Drilling Co. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 2230' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
3rd plug at 600' with 40 sx cement, 4th plug at 330' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 a.m. Day: 12 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement,
2nd plug at 1200' with 80 sx cement, 3rd plug at 600' with 40 sx cement,
4th plug at 330' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

I (operator) observe this plugging.

INVOICED

DATE 8-19-97

INV. NO. 68816

Signed _____
(TECHNICIAN)

8-15-97