

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21787-00-00
Spot: SWSENW Sec/Twnshp/Rge: 8-19S-30W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: BRYANT A Well Number: 1
County: LANE Total Vertical Depth: 4640 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 710 PETROLEUM BUILDING 221 S BRO
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/2 . 80
Surface Casing: Size 8.625 feet: 206 WITH 160 SX CMT
Production: Size 5.5 feet: 4628 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/13/2001 12:50 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: CARL GILPIN Company: KNIGHTON OIL Phone: (785) 623-4081

Proposed Plugging Method: 1ST PLUG AT 1320' WITH 80 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 220' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/13/2001 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4570-73'. BP @ 4530'. PERFS AT 4498-4501, 4479-83'. LEFT A DUMP BAILER & COLLAR LOCATOR IN HOLE BELOW 4350'. STUCK IN HOLE. CIBP @ 4350' & 4 SX CMT. 1ST PLUG AT 1300' WITH 80 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 220' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1300' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED

NOV 30 2001
11-30-01
KCC WICHITA

INVOICED

DATE 12-3-01 NOV 14 2001

TRV. NO. 2002061002

Form C-2/3

MP