

1070851

9-12

101-20,327-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

C SE SW, SEC. 13, T 19 S, R 30 W/E

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Clark Well # 2

Operator: Murfin Drilling Company  
Name & Address 250 N. Water, Suite 300

County Lane 151.93

Well Total Depth 4675 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 12 Month: 9 Year: 19 90

Plugging proposal received from Ed Lofland

(company name) Murfin Drilling Company (phone) 316-267-3241

were: 5 1/2" at 4672' w/1400 gal. Latex. Perfs at 4402-80'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,

2nd plug perforate at 1300', squeeze 50 sx cement and 5 sx gel at 900',

3rd plug at free point with 5 sx gel and 50 sx cement, 4th plug at 360' w/40 sx cement,

5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 9 p.m. Day: 12 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

2nd plug perforated at 1300' and squeezed 100 sx cement (50 sx in/50 sx out), shot off pipe at 740',

3rd plug pulled to 660' and pumped 5 sx gel and 50 sx cement,

9-18-90

4th plug pulled casing to 360' and pumped 2 sx gel and 40 sx cement,

5th plug pumped 10 sx cement at 40-0'

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 740' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-25-90

Signed Dan Johnson (TECHNICIAN)

INV. NO. 29425 9-12