

1 070010

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,194 - ~~0000~~

C NW NW, SEC. 30, T 19S, R 30 W/E  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9726

Lease Name A. Goering Well # 1

Operator: Gruss Petroleum Management, Inc.  
Name & Address 900 Building of the Southwest  
Midland, TX 79701

County Lane 152.43  
Well Total Depth 4690 (Mississippi) feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 11:35 am Day: 18 Month: July Year: 19 85

Plugging proposal received from Earl Levea

(company name) Gruss (phone) 915-682-8319  
Elevation 2930'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2200'

1st plug at 2200' with 50 sx cement

2nd plug at 1150' with 50 sx cement

3rd plug at 380' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement  
Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 1:45 pm Day: 18 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1150' with 50 sx cement, 3rd plug at 380' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell  
(if additional description is necessary, use BACK of this form.)

INVOICED (not) observe this plugging.

DATE AUG 01 1985

Signed Dan Gordon (TECHNICIAN)

INV. NO. 1258

7-26-85