

1080233

TO: STATE CORPORATION COMMISSION *12-2*

API NUMBER 15-101-20,628-0000  
NW NE NW SEC. 4, T 17 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 550 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1770 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME DUESER A WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 151.13

OPERATOR LICENSE # 31627 WELL TOTAL DEPTH 4650 FEET

OPERATOR: WHITETAIL CRUDE, INC PRODUCTION CSG: SIZE 4 1/2" @ 4649' WITH 200 SX

NAME AND PO BOX 544 SURFACE CASING: SIZE 8 5/8" @ 364' WITH 275 SX

ADDRESS NESS CITY, KS 67560

ABANDONED OIL WELL  GAS WELL  INPUT WELL  INJ WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR FRITZLER TRUCKING, INC LICENSE NUMBER NA

ADDRESS PO BOX 544, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 02 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE FRITZLER

(COMPANY NAME) FRITZLER TRUCKING, INC (PHONE) 785-798-3641

WERE: PERFS AT 4450-53 4520-25

1ST PLUG 25 SX CEMENT WITH 100# HULLS DISPLACED TO 4400' MAXIMUM PSI PRESSURE AT 1500#.

SHUT IN AT 1000#. 2ND PLUG PERFORATE 4 1/2 AT 1200'. ALLIED PUMPED DOWN 4 1/2 50 SX CEMENT

WITH 50# HULLS MIXED IN LAST 20 SX CEMENT, DISPLACED TO 900". MAXIMUM PSI AT 1500#. SHUT

WELL DOWN TO 0# BUT STAYED LOADED. 3RD PLUG SHOT CASING AT 766' PULLED UP TO 600' PUMP 40

SX CEMENT. 4TH PLUG PULLED UP TO 375' PUMPED 40 SX CEMENT. 5TH PLUG PULLED UP TO 40'

PUMPED 20 SX. HOLE STAYED LOADED. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 1:40 PM DAY: 02 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG 25 SX CEMENT WITH 100# HULLS DISPLACED TO 4400'. MAXIMUM

PSI AT 1500#. SHUT IN AT 1000#. 2ND PLUG LOG-TECH PERFORATED 4 1/2 AT 1200'. ALLIED PUMPED

DOWN 4 1/2 50 SX CEMENT WITH 50# HULLS MIXED IN LAST 20 SX CEMENT. DISPLACED TO 900'. MAXIMUM

PSI AT 1500#. SHUT DOWN WELL WENT TO 0# BUT STAYED LOADED. 3RD PLUG LOG-TECH SHOT CASING

AT 766' PULLED UP TO 600' PUMP 40 SX CEMENT. 4TH PLUG PULLED UP TP 375' PUMPED 40 SX

CEMENT. 5TH PLUG PULLED UP TO 40' PUMPED 20 SX CEMENT. HOLE STAYED LOADED.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 766' OF 4 1/2' CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin Strube  
(TECHNICIAN) FORM CP-2/3

*RAWZ*

DEC 16 1998

60450