

To: 1 051452
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5363
Operator: BEREXCO
Name & Address: P.O. Box 723
Hays, KS 67601

7-1
API NUMBER 15- 101-21,129-0000
E/2 E/2 NE, SEC. 4, T. 17 S, R. 29 W/E
3960 feet from S section line
330 feet from E section line
Lease Name Southern Well # 1
County Lane Lane 150.47
Well Total Depth 4630 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address _____

Company to plug at: Hour: 11 a.m. Day: 1 Month: 7 Year: 19 91

Plugging proposal received from Bob Grote

(company name) BEREXCO (phone) 913-628-6101

were: 4 1/2" at 4629' w/225 sx cement, PBSD 4565', Perfs at 4036-38, 4524-28'

Port collar at 2144' w/575 sx cement

1st plug pump 400 lbs. hulls, 200 sx cement down the 4 1/2",

2nd plug pump 15 sx cement down 8 5/8" X 4 1/2".

RECEIVED
STATE CORPORATION COMMISSION
JUL 08 1991
07-08-1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:25 p.m. Day: 1 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 8 5/8" X 4 1/2" with 15 sx cement, Maximum pressure 600 psi and shut in 500 psi.

2nd plug pumped 400 lbs. hulls and 200 sx cement down 4 1/2". Maximum pressure 1300 psi and shut in 1000 psi.

Remarks: Used 65/35 Pozmix 8% gel by B.J. Titan. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (did / XXXX) reserve this plugging.

DATE 7-22-91
INV. NO. 32347

Signed Richard W. Lash
(TECHNICIAN)