

1090567

7-11

API NUMBER 15- 101-20,986-0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

NW SE NW, SEC. 3, T 17 S, R 29 W/XX

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Munsell Well # 2

Operator: A.L. Abercrombie, Inc.

County Lane 149.50

Name & Address Rt. 1, Box 56

Well Total Depth 4600 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 10:15 a.m. Day: 11 Month: 7 Year: 19 95

Plugging proposal received from Mike Myer

(company name) A.L. Abercrombie, Inc. (phone) 316-793-8186

were: 4 1/2" at 4590' w/225 sx cement, DVd @ 1422' w/600 sx cement, PBTD 4510',

Perfs at 4190-93, 4216-18, 4316-18, 4475-77, 4484-86, 4490-95, 4520-22, 4527-29'

1st plug fill 4 1/2" casing with hulls and cement.

Check backside.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1995

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 11 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 6 sx hulls and 200 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Hooked onto backside. Shut in pressure 300 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-19-95

INV. NO. 43111

Signed [Signature] (TECHNICIAN)