

1080168

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,990-0000

SW SW SE, SEC. 25, T 19 S, R 30 W330 feet from W/S section line2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Anchor Well # 1Operator: The Dane G. Hansen TrustCounty LaneName & Address P. O. Box 187Well Total Depth 4638 150.74 feetLogan, KS 67646Conductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 330Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Galloway Drilling Co., Inc. License Number 5783Address 340 Broadway Plaza Bldg., 105 S. Broadway, Wichita, KS 67202Company to plug at: Hour: 2:30 pm Day: 22 Month: June Year: 19 84Plugging proposal received from McGuire(company name) Galloway (phone) 316-263-1793were: to fill hole with heavy mud and spot cement through drill pipe1st plug at 2180' with 50 sx cement2nd plug at 1000' with 40 sx cement3rd plug at 380' with 40 sx cement
solid bridge4th plug hulls - plug at 40' -- cement to surface with 10 sx cement6th plug to circulate rat hole with 10 sx cementPlugging Proposal Received by J. A. Trip
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 5:00 pm Day: 22 Month: June Year: 19 84ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement, 2nd plug at 1000' with 40sx cement, 3rd plug at 380' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
6-29-84
JUN 29 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

I, W. A. D. (not) observe this plugging.DATE 7-3-84Signed J. A. Trip
(TECHNICIAN)WV. NO. 520