

1060136

TO: STATE CORPORATION COMMISSION

12-1

API NUMBER 15-101-20,568-6000
NE NW SEC. 36, T 19 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CLARK WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 151.32

OPERATOR LICENSE # 31627

WELL TOTAL DEPTH 4656 FEET

OPERATOR: WHITETAIL CRUDE, INC

PRODUCTION CSG: SIZE 4 1/2" @ 4655' WITH 150 SX

NAME AND PO BOX 544

SURFACE CASING: SIZE 8 5/8" @ 342' WITH 225 SX

ADDRESS NESS CITY, KS 67560

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 4:50 PM DAY: 30 MONTH: 11 YEAR: 1998
HOUR: 9:00 AM DAY: 01 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 4605-11

1ST PLUG SANDED BACK TO 4300' WITH 4 SX CEMENT ON TOP. 2ND PLUG PERFORATE AT 1300'.

PUMPED 50 SX CEMENT AND 50# HULLS IN LAST 15 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT, 4TH PLUG AT 350' WITH 40 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 30 MONTH: 11 YEAR: 1998
HOUR: 11:30 AM DAY: 01 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 4300' WITH 4 SX CEMENT ON TOP. 2ND PLUG PERFORATE AT 1300'.

PUMPED 50 SX CEMENT AND 50# HULLS IN LAST 15 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT, 4TH PLUG AT 350' WITH 40 SX CEMENT,

5TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 761' OF 4 1/2' CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael G. Maier (TECHNICIAN) FORM CP-2/3

DEC 16 1998

60450

RMZ