

To: 1 020895
STATE CORPORATION COMMISSION
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

8-4

API NUMBER 15- 101-21,703-0000

PLUGGING SECTION W/2 NW NE, SEC. 36, T 19 S, R 30 W/E
4620 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Clark Well # 4

Operator: The Dane G. Hansen Trust

County Lane 151.45

Name & Address P.O. Box 187

Well Total Depth 4660 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530-1413

Company to plug at: Hour: Day: 4 Month: 8 Year: 1995

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Co., Inc. (phone) 316-792-5633

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2216'

1st plug at 2216' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 370' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 4 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2216' with 50 sx cement,

2nd plug at 1150' with 80 sx cement, 3rd plug at 650' with 50 sx cement,

4th plug at 370' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If not) observe this plugging.

DATE 8-18-95 Signed Glenn R. Barlow (TECHNICIAN)

WV. NO. 43325 8-4