

6 070819

12-27

API NUMBER 15- 051-01704-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW , SEC. 17 , T 14 S, R 19 W ~~XXXX~~

1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5252

Lease Name Meier Well # 2

Operator: R. P. Nixon Oper. Inc.

County Ellis 124.22

Name & Address 207 West 12th

Well Total Depth 3822 feet

Hays, Ks. 67601

Conductor Pipe: Size 0 feet

Dan Nixon

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor R. L. Titan and Co. tools License Number _____

Address Hays, Ks.

Company to plug at: Hour: PM Day: 27 Month: Dec Year: 19 89

Plugging proposal received from Mr. Dan Nixon

(company name) R. P. Nixon Oper Inc. (phone) _____

were: 8 5/8" - 200' s.p. cwc w/n.a. 5 1/2" casing at 3817' w/n.a. Elv. 2090 - anhy
1463' Casing leak in 5 1/2" (Dakota) R. P. Nixon said cement in annulus. Proposal Perf.
at 1473'. Order 375 sks 65/35 poz 8% gel and 5 sks hulls. Pump in with pump truck. Spot
through tubing. Load both 5 1/2" casing and 5 1/2" and 8 5/8" annulus with cement. Shut in
under pressure.

Plugging Proposal Received Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:20PM Day: 27 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Nixon ordered 375 sks 65/35 poz and 6% gel and five sks hulls
Pumped in with pump truck, spotted through tubing. (1) Perf at 1473'. Mr. Nixon said
said there was cement in annulus at surface. (2) Annulus open 2 3/8" tubing at 3800'.
Spotted 100 sks cement w/1 sk hulls and displaced. (3) 2 3/8" tubing at 2300' w/245 sks
cement w/2 1/2 sks hulls cement circulated out of 5 1/2" casing. (4) Squeezed 5 1/2" casing w/30 sks
cement. Max pressure 550 psi. Shut in at 350 psig. (5) Pressured annulus to 450 psig. Shut
in at 450 psig. Did not take cement. Cemented by B. J. Titan

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

INVOICED

JAN 24 1990

DATE _____

INV. NO. 27135

Signed Marion J. Schmidt
(TECHNICIAN)

Marion J. Schmidt

FORM CP-2/3
Rev. 01-84

RECEIVED
STATE CORPORATION COMMISSION
1-17-90
JAN 17 1990