

1 010104

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,297-~~6000~~

NW SE SW, SEC. 1, T 20 S, R 29 W/E<sup>X</sup>

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Lease Name McMillen Well # 1

Operator: Midco Exploration, Inc.

County Lane 152.43

Name & Address 200 E. 1st Street, Suite 411

Well Total Depth 4690 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 12:00 pm Day: 15 Month: March Year: 19 86

Plugging proposal received from Martin Miller

(company name) Blue Goose (phone) 316-792-5633

Elevation 2814'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2143-72'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1/2 the Anhydrite plus 300' with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Jack L. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:50 pm Day: 15 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2172' with 50 sx cement, 2nd plug at 1386' with 80

sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1986

3-20-86

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this report)

INVOICED

DATE MAR 20 1986

INV. NO. 13028

3-15

Signed Jack L. Luthi  
(TECHNICIAN)