

1050200

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION N/2 NW SE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,968 -0000  
SEC. 2, T 20 S, R 29 W

2310 feet from N/S section line  
1990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name McCoy Well # 1

Operator: Energy Exploration, Inc.

County Lane

Name & Address 1002 South Broadway

Well Total Depth 4990 162.18 feet

Wichita, KS 67211

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:30 p Day: 25 Month: April Year: 19 84

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling (phone) 913-726-4850

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2160' with 50 sx cement 2nd plug at 1110' with 50 sx cement

3rd plug at 750' with 50 sx cement 4th plug at 420' with 40 sx cement

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 10 sx cement

Plugging Proposal Received by Richard W. Lacy (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 am Day: 26 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement, 2nd plug at 1110' with

50 sx cement, 3rd plug at 750' with 50 sx cement, 4th plug at 420' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement, 7th plug to circulate rathole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

If additional description is necessary, use BACK of this form.

(did not) observe this plugging.

INVOICED

DATE 5-4-84

INV. NO. 1381

Signed Richard W. Lacy (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

MAY 03 1984

CONSERVATION DIVISION Wichita, Kansas

MAY 18 1984