

11-14

To: 1 070810  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION N/2 NW SE, SEC. 2, T 20 S, R 29 W/8  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,968-0001

2310 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5107

Lease Name McCoy Well # 1

Operator: H-30 Inc.  
Name & Address: 251 North Water, Suite 10  
Wichita, KS 67202

County Lane 149.37

Well Total Depth 4596 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:15 a.m. Day: 14 Month: 11 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4550' PBSD 4453' Perfs at 4313-14, 4472-76' Elevation 2837'KB  
1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 14 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4105' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. cement released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 1000 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1515' of 4 1/2" casing  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION RECEIVED  
NOV 13 1988  
11-18-88  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (If you observe this plugging.)

DATE 11-29-88

Signed Dan Anderson (TECHNICIAN)

INV. NO. 23148