

1 030779

1-22-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 10'W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,200 -0000
SE SW SE SEC. 2, T 20 S, R 29 W/E
330 feet from S section line
1660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name McCoy Well # 1

Operator: H-30, Inc.
Name & Address 251 North Water, Suite 10
Wichita, KS 67202

County Lane 153.08

Well Total Depth 4710 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service, Inc. License Number 6454

Address 118 North Penn, Ness City, KS

Company to plug at: Hour: 11:30 a.m. Day: 22 Month: 1 Year: 19 87

Plugging proposal received from Roger Pierson

(company name) Cheyenne Well Service, Inc. (phone) 316-798-2282

were: 4 1/2" at 4709' PBD 4709' Perfs at 4639-43', 4485-87'

1st plug set CIBP at 4400 and dump 2 sx cement on top,

2nd plug pump 3' sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

plug and pump 150 sx cement.

Plugging Proposal Received by Don C. Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 22 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4400' and dumped 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and released

8 5/8" wiper plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION

JAN 27 1987

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 600 psi and shut in 100 psi.

Remarks: Recovered 1750' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-29-87 observe this plugging.

Signed Steve Brunont
(TECHNICIAN)

INV. NO. 16013

1-22