

To: 1 052121 4-1  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-007-01,050-00-01  
C NE NE, SEC. 16, T 31 S, R 11 W/X  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5046  
Operator: Raymond Oil Company, Inc.  
Name:  
Address: P.O. Box 48788  
Wichita, KS 67201

Lease Name Axline Well # 1  
County Barber 128,96  
Well Total Depth 3968 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 156

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 1 Month: 4 Year: 19 97

Plugging proposal received from James Ray

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 3907', Perfs at 3772-3790'

1st plug sand back to 3720' and dump 4 sx cement on top of sand through bailer,

2nd plug at 720' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 150' with 40 sx cement, 5th plug at 40-0' with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12 p.m. Day: 1 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3720' and dumped 4 sx cement on top of sand through bailer,

Spotted through casing:

2nd plug at 720' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 150' with 40 sx cement,

5th plug at 40' with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED  
(If desired) observe this plugging.

DATE 4-10-97  
INV. NO. 47905

Signed Richard W. Lucy (TECHNICIAN)

RECEIVED  
HARISAS CORP COMM  
APR - 8 A D: 4:41  
4-8-97