

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20899-00-00
Spot: NWSWSWSW Sec/Twnshp/Rge: 3-35S-12W
659 feet from S Section Line, 4962 feet from E Section Line
Lease Name: LOHMANN Well #: 3-A
County: BARBER Total Vertical Depth: 4912 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4805		WITH 2 SX CMT
PROD	4.5	4911	0	WITH 100 SX CMT
SURF	8.625	305		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2013 8:45 AM
Plug Co. License No.: 34109 Plug Co. Name: M & M WELL SERVICE, LLC
Proposal Rcvd. from: ALAN VRATIL Company: VRATIL SERVICES Phone: (620) 886-2419

Proposed Plugging Method: RUN TBG TO 800' & CIRCULATE CMT. PRESSURE TEST 8 5/8" X 4 1/2" TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 07/11/2013 10:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****WELL SQUEEZED ON 10/28/10 AT 689'-722' & CIRCULATED CMT TO SURFACE UP 4 1/2"/8 5/8" ANNULUS** CIBP @ 4805' WITH 2 SX CMT. RUN TBG IN TO 796' CIRCULATE CMT TO SURFACE UP 4 1/2" CASING WITH 55 SX CMT. PRESSURE UP ON 8 5/8" X 4 1/2" ANNULUS TO 500#.**

Perfs:

Top	Bot	Thru	Comments
4850	4854		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA
JUL 18 2013
RECEIVED

District: 01

Signed

Richard M. Lacey
7/25/13

(TECHNICIAN)

RECEIVED

JUL 16 2013

KCC DODGE CITY

RAW