

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25717-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 32-17S-12W
1880 feet from S Section Line, 450 feet from E Section Line
Lease Name: BIEBERLE Well #: 10
County: BARTON Total Vertical Depth: 3375 feet

Operator License No.: 7030
Op Name: JOHN ROY EVANS OIL COMPANY LLC
Address: 405 FOURTH ST BOX 385
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	710		300 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/09/2013 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: DOUG Company: ROYAL DRILLING INC Phone: (785) 320-0030

Proposed Plugging Method: Ordered 190 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 01/09/2013 12:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3286 w/25 sx
2nd plug @750 w/40 sx
3rd plug @350 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

KCC WICHITA
JUL 23 2013
RECEIVED

District: 04

Signed C. Morris
(TECHNICIAN)

✓ 7/26/13

JUL 15 2013