

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00174-00-02
Spot: SESENW Sec/Twnshp/Rge: 8-11S-18W
2986 feet from S Section Line, 2974 feet from E Section Line
Lease Name: CAVE OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3598 feet

Operator License No.: 5565

Op Name: NATIONAL COOPERATIVE REFINERY

Address: 6000 W. 10TH
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10.75	174		
SURF	5.5	3592		

Assoc. (NCRA)

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/15/2013 9:00 AM

Plug Co. License No.: 34147

Plug Co. Name: ACE WELL SERVICE, INC.

Proposal Rcvd. from: KENT S. STOS

Company: NATIONAL COOPERATIVE REFIN

Phone: (620) 241-9221

Proposed
Plugging
Method:

Ordered 450 sx 60/40 pozmix 4 % gel cement w/500 # hulls.
Lans-3328' - 3474'
ARB-OH-3570' - 3598'
Junk in hole at 2900'
GPS: 39.11092 -099.34346
2996' FSL 3214' FEL SW SE SE NW

Plugging Proposal Received By: PAT STAAB

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/15/2013 12:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Pioneer perforating perforated at 1650' - 1394' and 224'.
Ace Well Service ran in hole with tubing to 2584'. SOS mixed and pumped 150 sx 60/40 pozmix w/300 # hulls mixed in.
Pulled tubing to 1650', mixed and pumped 135 sx cement w/200 # hulls mixed in.
Cement circulated up 5 1/2" casing and 10 3/4" casing. Shut in 10 3/4" casing.
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 60 sx cement to pressure up 5 1/2" casing and 10 3/4" casing with 200 psi and 200 psi shut in pressure.

Remarks: SOS TICKET # 1066

Plugged through: TBG

KCC WICHITA

JUL 23 2013

RECEIVED

District: 04

Signed

[Signature]
7/25/13
(TECHNICIAN)

CM

* REFER TO WELL CMT. RE: RESP.
PTY. PER LEGAL.

JUL 16 2013