

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20066-00-00
Spot: W2SWNW Sec/Twnshp/Rge: 12-14S-14W
3300 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BRANDENBERG Well #: 2
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 6867
Op Name: STEINLE, LA VERN DBA STEINLE OIL
Address: 624 E 3RD
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2759		
SURF	8.625	250		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2013 8:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: TIM BILLERY Company: SUPER OILWELL SERVICE Phone: (785) 324-2169

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 1500', 825', 205'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2013 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2300' and pumped 125 sx cement w/300 # hulls.
Pulled tubing to 825' and pumped 105 sx cement w/200 # hulls.
Cement circulated.
POOH. Hooked to casing and pumped 30 sx cement w/150 # hulls at 275 psi to shut in.
Hooked to braden head and pumped 5 sx cement at 200 psi.
GPS: 38.85087 -098.83487

Remarks: QUALITY CEMENTING TICKET # 7415

Plugged through: TBG

KCC WICHITA
JUL 23 2013
RECEIVED

District: 04

Signed Ray Dinkel
7/26/13 (TECHNICIAN)

CM

JUL 16 2013