

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20437-00-00
Spot: SWNWNWSE Sec/Twnshp/Rge: 14-28S-27W
2217 feet from S Section Line, 2415 feet from E Section Line
Lease Name: ENSIGN UNIT Well #: 1-14
County: GRAY Total Vertical Depth: 6235 feet

Operator License No.: 34472
Op Name: SUNFLOWER ENERGY, LLC
Address: 10801 MASTIN, STE 920
OVERLAND PARK, KS 66210

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1766		WITH 580 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/03/2013 6:00 AM
Plug Co. License No.: 34127 Plug Co. Name: TOMCAT DRILLING LLC
Proposal Rcvd. from: DAVID RICE Company: CRWON CONSULTING Phone: _____

Proposed Plugging Method: 1ST PLUG AT 1790' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/03/2013 8:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1790' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

KCC WICHITA
JUL 18 2013
RECEIVED

District: 01

Signed

Michael Maier
7/26/13
(TECHNICIAN)

RECEIVED

JUL 16 2013

KCC DODGE CITY

RAY