

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20450-00-00
Spot: E2NWSE Sec/Twnshp/Rge: 9-21S-6W
1980 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BROWN D Well #: 1
County: RICE Total Vertical Depth: 3494 feet

Operator License No.: 33838
Op Name: GIVENS, BRET
Address: 1300 N GRAND
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3480		150 SX
SURF	8.625	225		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2013 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/02/2013 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3430' AND CAP WITH 5 SX'S CEMENT. CHECKED CASING STRETCH --ONLY 2 INCHES. DECIDED TO PERFORATE AT 950', 550' AND 275'. RUN TUBING TO 950' AND PUMPED 12 SX'S GEL FOLLOWED BY 35 SX'S CEMENT, PULL TUBING TO 550' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 275' AND CIRCULATE CEMENT TO SURFACE--DID NOT GET CIRCULATION ON BACKSIDE OF 5.5". RAN 1" TUBING DOWN BACKSIDE AS FAR AS COULD GET--AROUND 180', AND CIRCULATED CEMENT TO SURFACE. PULL 1" OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3478	3482	CSG	

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS. TICKET #7502. COPELAND TICKET #C-41078.

Plugged through: TBG

KCC WICHITA
JUL 19 2013
RECEIVED

District: 02

Signed Virgil Clothier
7/25/13 (TECHNICIAN)