

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21969-00-00  
Spot: SWSWNESW Sec/Twnshp/Rge: 3-21S-6W  
1645 feet from S Section Line, 3727 feet from E Section Line  
Lease Name: CONRAD WEST Well #: 2  
County: RICE Total Vertical Depth: 3481 feet

Operator License No.: 33838  
Op Name: GIVENS, BRET  
Address: 1300 N GRAND  
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3493	969	200 SX
SURF	10.75	208		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2013 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/09/2013 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3340' AND CAP WITH 7 SX'S CEMENT. SHOOT CASING OFF @ 969' AND PULL OUT OF HOLE. RUN TUBING TO 950' AND PUMP 12 SX'S GEL, FOLLOWED BY 50 SX'S CEMENT. PULL TUBING TO 550' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 250 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3404	3410	CSG	

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #7519. COPELAND TICKET #41084.

Plugged through: TBG

KCC WICHITA

JUL 19 2013

RECEIVED

District: 02

Signed

Virgil Clothier  
7/25/13 (TECHNICIAN)