

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26537-00-00
Spot: S2N2N2NE Sec/Twnshp/Rge: 33-13S-16W
517 feet from N Section Line, 1320 feet from E Section Line
Lease Name: RUNWAY UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3175		
PROD	5.5	3498		130 SX
SURF	8.625	262		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2013 7:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERING Company: DAMAR RESOURCES, INC. Phone: (785) 623-3221

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cut casing at 2517' leaving 981' of 5 1/2" casing in hole.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2013 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Set CIB plug at 3175' and spotted 1 sx cement on top.
Cut casing at 2517'.
Pulled casing to 1647' and pumped 125 sx cement w/300 # hulls.
Pulled casing to 1100' and pumped 40 sx cement w/100 # hulls.
Pulled casing to 220' and pumped 50 sx cement.
Cement circulated.
POOH. Cellar stayed full of cement.
60 Joints of 5 1/2" casing recovered.

GPS: 38.88444 -099.10004

Perfs:

Top	Bot	Thru	Comments
3227	3297		

Remarks: QUALITY CEMENTING TICKET 7261

Plugged through: CSG

KCC WICHITA
JUL 23 2013
RECEIVED

District: 04

Signed

Ray Dinkel
7/25/13

(TECHNICIAN)

CM

JUL 16 2013