

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-02125-00-00  
Spot: SENENE Sec/Twnshp/Rge: 22-14S-12W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MILLER Well #: 4  
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3279       |             | 100 SX   |
| SURF   | 8.625 | 225        |             | 150 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2013 2:30 PM  
Plug Co. License No.: 34147 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: MIKE KERNS Company: PINTAIL PETROLEUM, LTD. Phone: (785) 623-3780

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Perforations: 1500', 650' and 230'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/11/2013 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2870' and pumped 50 sx cement.  
Pulled tubing to 2075' and pumped 125 sx cement w/400 # hulls.  
POOH. Hooked to casing and pumped 60 sx cement w/100 # hulls.  
Cement circulated out braden head.

GPS: 38.82486 -098.63354

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3234 | 3242 |      |          |

Remarks: QUALITY CEMENTING TICKET # 7417

Plugged through: TBG

KCC WICHITA

JUL 23 2013

RECEIVED

District: 04

Signed

Ray A. Dinkel

7/26/13

(TECHNICIAN)

CM

JUL 16 2013