

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01373-00-01
Spot: NWSENE Sec/Twnshp/Rge: 31-8S-17W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: RUSS Well #: 2
County: ROOKS Total Vertical Depth: 1695 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY STE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3359		
SURF	8.625	208		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/30/2012 12:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: CORY Company: CONTINENTAL OPERATING Phone: (785) 259-2851

Proposed Plugging Method: Ordered 490 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 10/31/2012 12:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

10/30 Hooked up to 5 1/2 casing mixed & pumped 150sx & 500# hulls, shut down for one hour. Ran tubing to 1640', mixed & pumped 200sx, shut down for one hour. Pulled 15 jts. of tubing mixed & pumped 80sx. Pulled tubing. 10/31 Ran tubing to 240', tagged cement, hooked up, mixed & pumped 50sx, cement circulated. Topped off casing with 10sx.

Perfs:

Remarks: QUALITY

Plugged through: TBG

KCC WICHITA

JUL 23 2013

RECEIVED

District: 04

Signed _____

Case Morris
7/26/13 (TECHNICIAN)

JUL 15 2013