

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00563-00-00
Spot: NESWNW Sec/Twnshp/Rge: 33-5S-20W
1650 feet from N Section Line, 990 feet from W Section Line
Lease Name: HANSEN B Well #: 7
County: PHILLIPS Total Vertical Depth: 3579 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3565		150 SX
SURF	8.675	187		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2013 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 689-7567

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations at 3565' - 3579'
Perforated at 1750' and 1060'.
Casing leaks at 2641' and 2354' - 2387'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2013 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3454' and pumped 150 sx cement w/200 # hulls.
Pulled tubing to 2000' and pumped 150 sx cement w/200 # hulls.
Pulled tubing to 950' and pumped 75 sx cement w/100 # hulls to circulate cement to surface.
Pulled all tubing and topped off 5 1/2" casing w/125 sx cement.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 50 sx cement. Maximum pressure 100 psi.
GPS: 39.57734N -099.58685W

Perfs:

Top	Bot	Thru	Comments
3565	3579		

Remarks: SWIFT SERVICES TICKET # 24878

Plugged through: TBG

KCC WICHITA

JUL 23 2013

RECEIVED

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

3/25/13

CM

JUL 15 2013