

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20587-00-00
Spot: W2NWSE Sec/Twnshp/Rge: 2-18S-43W
2004 feet from S Section Line, 2308 feet from E Section Line
Lease Name: COYOTE Well #: 2
County: GREELEY Total Vertical Depth: 5290 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		2005		WITH 450 SX CMT
PROD	5.5	5279	0	WITH 650 SX CMT
SURF	8.625	353		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2013 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (785) 798-5151

Proposed Plugging Method: CIBP @ 5100' WITH 2 SX CMT OR 30 SX CMT & 100# HULLS. FILL 5 1/2" WITH CMT FROM 2100' TO 0'. ATTEMPT TO PUMP INTO ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2013 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT WITH 100# HULLS AT 5075'. PUMP 260 SX CMT FROM 2115' TO 0' IN 2 STAGES INCLUDING TOP OFF. PUMP 10 SX CMT DOW THE ANNULUS TO 450#.

Perfs:

Top	Bot	Thru	Comments
5148	5158		

KCC WICHITA
JUL 22 2013
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED 10 YR TA** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JUL 19 2013

KCC DODGE CITY

Signed

[Signature]
7/26/13

(TECHNICIAN)

[Handwritten mark]