

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21326-00-00  
Spot: W2SESWNE Sec/Twnshp/Rge: 6-33S-29W  
2234 feet from N Section Line, 1760 feet from E Section Line  
Lease Name: ANGELL Well #: 4-6  
County: MEADE Total Vertical Depth: 6190 feet

Operator License No.: 33600  
Op Name: EVANS ENERGY, LLC  
Address: PO BOX 8  
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	64		WITH 230 SX CMT
PROD	5.5	5820	3220	WITH 700 SX CMT
SURF	8.625	1620		WITH 165 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/05/2013 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: CHASE EVANS Company: EVANS ENERGY Phone: (620) 532-3711

Proposed Plugging Method: SAND BACK PERFS TO 50' ABOVE PLUS 5 SX CMT. LOAD HOLE WITH GEL. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/05/2013 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED THE BOTTOM TO 5475' WITH 5 SX CMT. 1ST PLUG AT 1640' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 495' WITH 50 SX CMT 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5726	5731		
5526	5530		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

JUL 18 2013

RECEIVED

District: 01

RECEIVED

JUL 16 2013

KCC DODGE CITY

Signed Eric MacLaren  
7/25/13 (TECHNICIAN)