

State of Kansas



15-101-20091-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1974
3-15-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of DNB Drilling, Incorporated has this
date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Herndon Drilling Company,

Complete Address: P. O. Box #489, Tulsa, Oklahoma.

Lease Name: Stallken Well No. 1

Location: CSW-SW Sec. 23 Twp. 20 Rge. (E)(W) 30

County: Lane Total Depth 4710' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

311'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 525'.

Circulate hole with heavy mud. Pull DP to 750' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent