



15101 (FORM 6700)

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.,

Complete Address: Suite 800-200 West Douglas, Wichita, Kansas.

Lease Name: Leighton Well No. 1

Location: CSW-NE Sec. 28 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4640' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

296'--8 5/8" Surface casing, cement circulated with 200 Sx.
4640'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4600'. Top perforations @ 4053'.

Push plug to 4000', sand back to 3950' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

N. L. Nichols
Conservation Division Agent