



15-101-19026-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
3-30-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: Suite #800--200 West Douglas, Wichita, Kansas.

Lease Name: Leighton Well No. 2

Location: CNE-NE Sec. 28 Twp. 16 Rge. (E)(W)27

County: Lane Orig RTD 4550'  
Total Depth 1914' Oil Well

Gas Well  Input Well  SWD Well X D & A  Lost Hole

Mr. Kelso was instructed to plug the well as follows:

287'--8 5/8" Surface casing, cement circulated with 200 Sx.  
1952'--4 1/2" casing cemented with 350 Sx. Top perforations @ 1738'.  
4 1/2" plugged back to 1914'. Top of cement @ 400' (Temp. Survey).

Pull 4 1/2" casing and squeeze well with 1 sack hulls, 12 sacks gel and 80 Sx. cement staged.

Very truly yours,

  
Conservation Division Agent