



15-101-19030-07010

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 3 - 6 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Cebert Richter of Helmerich & Payne, Incorporated has this date requested permission to plug the following described well:

Mr. Richter guarantees payment of the plugging fee.

Operator's full Name: Helmerich & Payne, Incorporated,

Complete Address: 210 1/2 No. Main St., Garden City, Kansas.

Lease Name: Hall Well No. 1

Location: CNE-SW Sec. 28 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4303' Oil Well X

Gas Well      Input Well      sWD Well      D & A      Lost Hole     

Mr. Richter was instructed to plug the well as follows:

298'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4238' 4 1/2" Production casing cemented on bottom with 150 Sx. Bridge plug @ 4105'. Top perforations 4065'.

Sand well back to 4000' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing to 900' and circulate heavy gel mud and follow with 100 Sx. cement. Pull casing to 330 and displace 20 Sx. cement thru casing. Pull casing and fill hole to surface with cement.

Very truly yours,

Conservation Division Agent