

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24893-00-00
Spot: E2SWSNW Sec/Twnshp/Rge: 15-16S-12W
2970 feet from S Section Line, 3450 feet from E Section Line
Lease Name: KRAMER Well #: 5
County: BARTON Total Vertical Depth: 3519 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 15 S MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3424		175 SX
PROD	5.5	3434		175 SX
SURF	8.625	393		236 SX
T1	2.875	3400		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2013 9:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL CO Phone: (785) 483-1543

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

06/21/13-Ran tubing to 3400'. Pumped 300 # hulls with water and followed with 75 sx cement w/150 # hulls.
06/24/13-Cut casing at 1400'. Pulled casing to 1390' and pumped 150 sx cement w/200 # hulls.
Pulled casing to 950' and pumped 50 sx cement w/100 # hulls.
Pulled casing to 500' and pumped 50 sx cement w/100 # hulls.
Pulled casing to 250'. Circulated cement to surface with 50 sx cement.
Pulled casing. Hole stayed full.

GPS: 38.66047 -098.63918

Perfs:

Top	Bot	Thru	Comments
3433	3439		
3267	3270		
3248	3252		
3227	3231		
3120	3124		
3006			

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

Bruce Rodie
7/18/13

(TECHNICIAN)

CM

JUL 05 2013