

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23787-00-00
Spot: SWSENE Sec/Twnshp/Rge: 2-21S-13W
2296 feet from N Section Line, 1015 feet from E Section Line
Lease Name: ANDRESS B Well #: 1-2
County: STAFFORD Total Vertical Depth: 3635 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3628	1603	WITH 175 SX CMT
SURF	8.625	383		WITH 350 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/11/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SAND TO 3200' & 4 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2013 9:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3130' WITH 4 SX CMT ON TOP WITH BAILER. 1ST PLUG AT 775' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3525	3527		
3523	3525		
3512	3514		
3456	3457		
3455	3458		
3334	3336		
3321	3323		
3251	3254		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

KCC WICHITA
JUL 18 2013
RECEIVED

District: 01

Signed Richard M. Lacey
7/18/13 (TECHNICIAN)

RECEIVED
JUL 16 2013
KCC DODGE CITY