

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-01055-00-00  
Spot: NWSWNENW Sec/Twnshp/Rge: 6-21S-12W  
977 feet from N Section Line, 1556 feet from W Section Line  
Lease Name: ROSE OWWO Well #: 2  
County: STAFFORD Total Vertical Depth: 3600 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3595	1600	WITH 165 SX CMT
SURF	8.625	240		WITH 65 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2013 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: SAND BACK TO 60' ABOVE PERFS. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: NONE  
Date/Time Plugging Completed: 07/12/2013 3:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SANDED BACK TO 3260' WITH 4 SX CMT. 1ST PLUG AT 690' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 278' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3534	3538		
3506	3514		
3486	3492		
3448	3450		
3298	3300		
3269	3271		
3226	3232		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

KCC WICHITA  
JUL 18 2013  
RECEIVED

District: 01

Signed Nathan Willis  
7/18/13 (TECHNICIAN)

RECEIVED  
JUL 16 2013  
KCC DODGE CITY